





Isle of Palms Beach Restoration Project 2026

Charleston County, SC

TITLE	DRAWING No.
COVER SHEET	SHEET 01
OVERALL PROJECT PLAN & SURVEY CONTROL.....	SHEET 02
REACH 1 & 2 PLAN MAP AND SURVEY CONTROL.....	SHEET 03
REACH 3 PLAN MAP AND SURVEY CONTROL.....	SHEET 04
PROJECT PLAN & PROFILES - REACH 1	SHEET 05
FILL PLAN PROFILES - STA 314+00 TO 328+00.....	SHEET 06
PROJECT PLAN & PROFILES - REACH 2.....	SHEET 07
FILL PLAN PROFILES - STA 254+00 TO 280+00.....	SHEET 08
PROJECT PLAN & PROFILES - REACH 3.....	SHEET 09
FILL PLAN PROFILES - STA 22+00 TO 66+00.....	SHEET 10
FILL PLAN PROFILES - STA 70+00 TO 86+00.....	SHEET 11
NEARSHORE BATHYMETRY.....	SHEET 12
BORROW PLAN & CONTOURS.....	SHEET 13
BORROW BATHYMETRY & SECTIONS.....	SHEET 14
GEOTECHNICAL DATA - CORELOGS.....	SHEET 15
GEOTECHNICAL DATA - CORELOGS.....	SHEET 16



BID DOCUMENTS





Project No. 2623
Date: 17 July 2026



Owner:
City of Isle of Palms
1207 Palm Blvd.
Isle of Palms SC 29451

Engineer:
Coastal Science & Engineering, Inc.
160 Gills Creek Parkway
Columbia South Carolina 29209
Office 803-799-8949






Corridor Centerline Locations		
Area	Easting	Northing
Southern Corridor CL 1	2,378,668.73	345,127.83
Southern Corridor CL 2	2,369,883.29	346,688.70
Northern Corridor CL 1	2,384,133.92	347,666.12
Northern Corridor CL 2	2,390,592.42	356,037.36

Permit Borrow Area Coordinates		
Point	Easting	Northing
A	2,378,667.09	345,126.53
B	2,381,994.21	347,781.32
C	2,386,665.88	347,538.15
D	2,387,185.77	345,318.63
E	2,382,406.82	342,379.28

Borrow Area Information (See Sheets 13-16 for details)		
Borrow Area	Area (acres)	Available Volume For 10 ft Excavation (cy)
Total	650	~10,486,700
Priority	383	~6,179,100



Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 16 and 29 Jun 2026
Coastal Science & Engineering, Inc via RTK GPS

Key

———— Permitted Borrow Area

----- Priority Borrow Sections

Borrow Area cut depths varies as shown on Sheet 15

CLIENT:

CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:

ISLE OF PALMS
BEACH RESTORATION PROJECT

DRAWING TITLE:

OVERALL PROJECT PLAN
& SURVEY CONTROL

SCALE: AS SHOWN

DATE: 17 Jul 2026



DRAWN BY: SF/TH

APPROVED BY:

PROJECT #: 2623

SHEET NO:

02



PROJECT BASELINE COORDINATES		
POINT	EASTING	NORTHING
1 (222+00)	2,383,542.90	353,531.03
2 (280+00)	2,390,849.49	356,256.55
3 (328+00)	2,393,834.10	360,015.82
4 (376+00)	2,390,272.90	363,234.07

Control Coordinate Chart			
System: US State Plane Zone: SC 3900 Datum: NAD 1983 (ft)			
Monument	Easting	Northing	Elevation (ft NAVD)
3157 E	2,384,460.86	353,767.37	10.900
3159 B	2,385,426.67	354,203.23	5.850
3165 C	2,387,358.04	354,646.10	7.868
3167 E	2,388,809.51	355,220.97	6.871
3170 E	2,389,611.74	355,550.60	6.751
3173 E	2,390,859.15	356,219.80	10.894
3175 B	2,391,523.70	356,834.29	10.060
3178 E	2,392,124.80	357,653.02	9.956
3180 E	2,392,517.59	358,286.22	8.335
3183 E	2,393,214.45	359,050.21	7.100
3185 B	2,393,414.54	359,487.37	8.180
3190 B	2,392,408.57	361,004.31	4.640

Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 16 Jun 2026 Photo: 10 Jul 2026
Coastal Science & Engineering, Inc via RTK GPS

KEYNOTE
VA Vehicle Access
S Staging Area
P Daily Parking

Key
— Baseline
— Construction Plan
Fill Dune @ +14' NAVD
Fill Berm @ +6' to +7' NAVD
Fill Slope @ 1V:18H




CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:

**ISLE OF PALMS
BEACH RESTORATION PROJECT**



DRAWING TITLE:

**REACH 1 & 2 PLAN MAP AND
SURVEY CONTROL**



SCALE: AS SHOWN
DATE: 17 Jul 2026
DRAWN BY: SF/TH
APPROVED BY:
PROJECT #: 2623








SHEET NO:
03



Control Coordinate Chart			
System: US State Plane Zone: SC 3900 Datum: NAD 1983 (ft)			
Monument	Easting	Northing	Elevation (ft NAVD)
3100 B	2,365,850.66	345,201.78	7.91
3105B	2,366,847.16	345,256.90	7.94
3110 E	2,367,455.13	345,666.70	8.10
3115 E	2,369,276.39	346,815.40	9.00
3120 B	2,370,637.25	347,603.03	12.39
3125 B	2,372,935.39	349,041.15	8.17

- Key
- Baseline
 - Construction Plan
 - Fill Dune @ +14' NAVD
 - Fill Berm @ +6' to +7' NAVD
 - Fill Slope @ 1V:18H

PROJECT BASELINE COORDINATES		
POINT	EASTING	NORTHING
1 (0+00)	2,365,547.46	344,462.21
2 (86+00)	2,373,047.38	348,670.67



GRAPHIC SCALE (FEET)
100 0 100 200

Notes:

- The Engineer may modify the fill design within a reach for any portion of the project based on the beach condition at the time of construction.
- Fill May be placed in the extension areas based on conditions at time of the construction as directed by the Engineer.
- The landward limit of fill outside of the dune area is indicated based on approximate location of the +7 ft contour on 16 June 2026. The landward limit of fill will be the seaward edge of vegetation or the +7 ft NAVD contour; whichever is further seaward at the time of construction. In the dune area the landward limit of the fill will be at the +7 ft contour shown.
- Any non-vegetated beach area within the project limits may be used to stage equipment and temporarily store materials. Contractor shall not store materials on or damage vegetated dune areas without prior approval from the Engineer.
- The seaward limit of the berm will be built to an elevation of +6 ft (NAVD). The slopes and elevations are as noted on the drawing and sections.
- No fill will be placed on or landward of existing emergency control structures. Excess material may be stockpiled for later use by private homeowners. Stockpile material will be pay quantity.
- No work should be completed on or under private structures such as porches, walkovers or patios.
- Work within FWS Zone 1 must be started and completed from June 1 to November 30. Work Within FWS Zone 3 can be completed year round.

Section Notes:
Vertical Exaggeration: 15
Seaward Dune Slope: 1V on 4H
Landward Dune Slope: 1V on 2H
— Existing Surface
- - - Construction Fill

Survey Datum:
Horizontal: SPCS NAD '83 (Feet)
SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 16 Jun 2026
Photo: 10 Jul 2026
Coastal Science & Engineering, Inc
via RTK GPS

KEYNOTE
VA Vehicle Access
S Staging Area
P Daily Parking


Key
— Baseline
Fill Dune @ +14' NAVD
Fill Berm @ +6' to +7' NAVD
Fill Slope @ 1V:18H








CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:
ISLE OF PALMS
BEACH RESTORATION PROJECT

DRAWING TITLE:
REACH 1 - Project Plans and
Fill Sections
STA 290+00 to 310+00



SCALE:	AS SHOWN	SHEET NO: 05
DATE:	17 Jul 2026	
DRAWN BY:	SF/TH	
APPROVED BY:		
PROJECT #:	2623	



Section Notes:
Vertical Exaggeration: 15
Seaward Dune Slope: 1V on 4H
Landward Dune Slope: 1V on 2H
— Existing Surface
- - - Construction Fill

NOTE

Compensating slopes will be allowed for payment purposes. Contractor may construct a wider berm with steeper slope than identified in the plans to facilitate efficient construction. Compensating slopes should seek to place the design fill quantity at each section, and not exceed the volume tolerance (plus or minus 10%) for each fill section. Sand placed above the fill template along the slope will be considered pay quantity, up to 10% above the design fill volume for that section. Any sand placed seaward of the design toe of fill will not be considered pay quantity.


Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 16 Jun 2026
Coastal Science & Engineering, Inc via RTK GPS



CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:
ISLE OF PALMS
BEACH RESTORATION PROJECT








DRAWING TITLE:
**REACH 1 - Project Plans and
Fill Sections**
STA 314+00 to 328+00



SCALE: AS SHOWN
DATE: 17 Jul 2026
DRAWN BY: SF/TH
APPROVED BY:
PROJECT #: 2623

SHEET NO:

06



Section Notes:
Vertical Exaggeration: 15
Seaward Dune Slope: 1V on 4H
Landward Dune Slope: 1V on 2H
— Existing Surface
- - - Construction Fill

NOTE

Compensating slopes will be allowed for payment purposes. Contractor may construct a wider berm with steeper slope than identified in the plans to facilitate efficient construction. Compensating slopes should seek to place the design fill quantity at each section, and not exceed the volume tolerance (plus or minus 10%) for each fill section. Sand placed above the fill template along the slope will be considered pay quantity, up to 10% above the design fill volume for that section. Any sand placed seaward of the design toe of fill will not be considered pay quantity.

Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 16 Jun 2026
Coastal Science & Engineering, Inc via RTK GPS



CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:
ISLE OF PALMS
BEACH RESTORATION PROJECT








DRAWING TITLE:
**REACH 2 - Project Plans and
Fill Sections**
STA 256+00 to 280+00



SCALE: AS SHOWN
DATE: 17 Jul 2026
DRAWN BY: SF/TH
APPROVED BY:
PROJECT #: 2623

SHEET NO:

08



- Notes:
- The Engineer may modify the fill design within a reach for any portion of the project based on the beach condition at the time of construction.
 - Fill May be placed in the extension areas based on conditions at time of the construction as directed by the Engineer.
 - The landward limit of fill outside of the dune area is indicated based on approximate location of the +7 ft contour on 29 June 2026. The landward limit of fill will be the seaward edge of vegetation or the +7 ft NAVD contour; whichever is further seaward at the time of construction. In the dune area the landward limit of the fill will be at the +7 ft contour shown.
 - Any non-vegetated beach area within the project limits may be used to stage equipment and temporarily store materials. Contractor shall not store materials on or damage vegetated dune areas without prior approval from the Engineer.
 - The seaward limit of the berm will be built to an elevation of +6 ft (NAVD). The slopes and elevations are as noted on the drawing and sections.
 - No fill will be placed on or landward of existing emergency control structures. Excess material may be stockpiled for later use by private homeowners. Stockpile material will be pay quantity.
 - No work should be completed on or under private structures such as porches, walkovers or patios.
 - Work within FWS Zone 1 must be started and completed from June 1 to November 30. Work Within FWS Zone 3 can be completed year round.

Section Notes:

Vertical Exaggeration: 15

Seaward Dune Slope:1V on 4H

Landward Dune Slope:1V on 2H

Existing Surface

Construction Fill

Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 16 Jun 2026
Photo: 10 Jul 2026
Coastal Science & Engineering, Inc via RTK GPS

Key

Baseline

Fill Dune @ +14' NAVD

Fill Berm @ +6' to +7' NAVD

Fill Slope @ 1V:18H



CLIENT:


CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:

ISLE OF PALMS
BEACH RESTORATION PROJECT

DRAWING TITLE:

REACH 3 - Project Plans and
Fill Sections
STA 0+00 to 24+00



SCALE: AS SHOWN

DATE: 17 Jul 2026













DRAWN BY: SF/TH

APPROVED BY:

PROJECT #: 2623

SHEET NO:

09



NOTE

Compensating slopes will be allowed for payment purposes. Contractor may construct a wider berm with steeper slope than identified in the plans to facilitate efficient construction. Compensating slopes should seek to place the design fill quantity at each section, and not exceed the volume tolerance (plus or minus 10%) for each fill section. Sand placed above the fill template along the slope will be considered pay quantity, up to 10% above the design fill volume for that section. Any sand placed seaward of the design toe of fill will not be considered pay quantity.

Reach 3 dune alignment and position may be adjusted in the field at the Engineer's discretion based on conditions during time of construction.

Section Notes:

Vertical Exaggeration: 15
Seaward Dune Slope: 1V on 4H
Landward Dune Slope: 1V on 2H
— Existing Surface
- - - Construction Fill

Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 29 Jun 2026
Coastal Science & Engineering, Inc via RTK GPS



CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:
ISLE OF PALMS
BEACH RESTORATION PROJECT





DRAWING TITLE:
REACH 3 - Project Plans and
Fill Sections
STA 28+00 to 72+00



SCALE: AS SHOWN
DATE: 17 Jul 2026
DRAWN BY: SF/TH
APPROVED BY:
PROJECT #: 2623

SHEET NO:

10



Section Notes:
Vertical Exaggeration: 15
Seaward Dune Slope: 1V on 4H
Landward Dune Slope: 1V on 2H
— Existing Surface
- - - - - Construction Fill

NOTE

Compensating slopes will be allowed for payment purposes. Contractor may construct a wider berm with steeper slope than identified in the plans to facilitate efficient construction. Compensating slopes should seek to place the design fill quantity at each section, and not exceed the volume tolerance (plus or minus 10%) for each fill section. Sand placed above the fill template along the slope will be considered pay quantity, up to 10% above the design fill volume for that section. Any sand placed seaward of the design toe of fill will not be considered pay quantity.

Reach 3 dune alignment and position may be adjusted in the field at the Engineer's discretion based on conditions during time of construction.


Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Dates: 29 Jun 2026
Coastal Science & Engineering, Inc via RTK GPS



CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451


PROJECT:
ISLE OF PALMS
BEACH RESTORATION PROJECT

DRAWING TITLE:
REACH 3 - Project Plans and
Fill Sections
STA 76+00 to 86+00



SCALE: AS SHOWN
DATE: 17 Jul 2026
DRAWN BY: SF/TH
APPROVED BY:
PROJECT #: 2623

11



Corridor Centerline Locations		
Area	Easting	Northing
Southern Corridor CL 1	2,378,668.73	345,127.83
Southern Corridor CL 2	2,369,883.29	346,688.70
Northern Corridor CL 1	2,384,133.92	347,666.12
Northern Corridor CL 2	2,390,592.42	356,037.36

Borrow Area Coordinates		
Point	Easting	Northing
A	2,378,667.09	345,126.53
B	2,381,994.21	347,781.32
C	2,386,665.88	347,538.15
D	2,387,185.77	345,318.63
E	2,382,406.82	342,379.28

Survey Datum:
Horizontal: SPCS NAD '83 (Feet) SC Zone 3900
Vertical: NAVD '88 (Feet)
Coastal Science & Engineering, Inc via RTK GPS
Pipeline Corridors are 600' wide

Legend

- Permitted Borrow Area
- Priority Borrow Area



CLIENT:


CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451

PROJECT:

ISLE OF PALMS
BEACH RESTORATION PROJECT

DRAWING TITLE:

Nearshore Bathymetry



SCALE: AS SHOWN
DATE: 17 Jul 2026
DRAWN BY: SF/TH
APPROVED BY:
PROJECT #: 2623

SHEET NO:


12

Borrow Area Coordinates		
Point	Easting	Northing
A	2,378,667.09	345,126.53
B	2,381,994.21	347,781.32
C	2,386,665.88	347,538.15
D	2,387,185.77	345,318.63
E	2,382,406.82	342,379.28

Borrow Area Acreage and Volume			
Area	Acre	Volume (CY)	Max Depth of Cut (ft)
Priority Borrow Area	~383	~6,179,100	10.00
Supplemental Area 1	~13	~83,900	4.00
Supplemental Area 2	~64	~616,770	6.00
Supplemental Area 3	~44	~571,460	8.00

Corridor Centerline Locations		
Area	Easting	Northing
Southern Corridor CL 1	2,378,668.73	345,127.83
Southern Corridor CL 2	2,369,883.29	346,688.70
Northern Corridor CL 1	2,384,133.92	347,666.12
Northern Corridor CL 2	2,390,592.42	356,037.36

Note:
Coordinates for permitted areas are shown
on this drawing. Digital files of all areas
shall be provided upon request.



Datum:
Horizontal: NAD'83 SPCS (feet)
SC Zone 3900
Vertical: NAVD '88 (FEET)
Contours Shown in feet (NAVD) based on data collected March 2024.

0 300
Scale (Feet)

Legend


- Permitted Borrow Area
- Priority Borrow Area
- Supplemental Borrow Areas



CLIENT:
CITY OF ISLE OF PALMS
1207 PALM BLVD.
ISLE OF PALMS SC 29451



PROJECT:
ISLE OF PALMS
BEACH RESTORATION PROJECT

DRAWING TITLE:
Borrow Area
Bathymetry & Contours



SCALE:	AS SHOWN
DATE:	17 July 2026
DRAWN BY:	SF/TH
APPROVED BY:	
PROJECT #:	2623

SHEET NO:
13



CORE LOG				Coastal Science & Engineering				Sheet #1 of 1	
PROJECT		2589 - Isle of Palms Mar		COORDINATES		HOLE NUMBER			
LOCALITY				Northing: 0.000 Easting: 0.000 Grid Datum: NAD '83		IOP-2			
DATE				TOP ELEVATION		DEVICE DESIGNATION		Coastal Science & Engineering	
BORE ANGLE		90.00°		BOTTOM ELEVATION		BARREL SIZE/TYPE		3 in. Aluminum	
BURDEN THICKNESS		7.8 ft.		WATER DEPTH		GEOLOGIST FIELD TEAM			
CORE RECOVERY		7.8 ft. (100.0%)		geophysical data only					
Depth	Interval	Classification Of Materials (Description)				Sample	Remarks		
1	0.0 to 2.8 ft	Fine Sand - dark grey				S1	0.0 to 2.8 ft. to 2.8 ft. Shell: 0.0% Mean Grain Size: 0.130mm		
2	2.8 to 3.7 ft	Shell Clusters							
3	3.7 to 5.0 ft	Medium Sand / Coarse Sand mix - lot of shell fragments				S2	2.8 ft. to 5.0 ft. Shell: 12.1% Mean Grain Size: 0.140mm		
4	5.0 to 6.2 ft	Fine Sand - medium grey				S3	5.0 to 6.2 ft. to 6.2 ft. Shell: 42.1% Mean Grain Size: 0.130mm		
5	6.2 to 7.8 ft	Fine Sand / Medium Sand mix - dark grey				S4	6.2 to 7.8 ft. to 7.8 ft. Shell: 12.1% Mean Grain Size: 0.130mm		
6	7.8 to 8.0 ft	Shell Fragment							
7	8.0 to 8.2 ft	Clay lens							
8	8.2 to 8.4 ft	Clay lens							
9	8.4 to 8.6 ft	Clay lens							
10	8.6 to 8.8 ft	Clay lens							

CORE LOG				Coastal Science & Engineering				Sheet # of 1	
PROJECT		2589 - Isle of Palms Mar		COORDINATES		HOLE NUMBER		IOP-12	
LOCALITY		DATE		Nothing 0.000 Eastng 0.000 Grid Datum NAD '83		DEVICE		Coastal Science & Engineering	
BORE ANGLE		90.00°		TOP ELEVATION		DESIGNATION		3 in. Aluminum	
BUREN THICKNESS		9.2 Ft.		BOTTOM ELEVATION		BARREL SIZE/TYPE			
CORE RECOVERY		9.2 Ft. (100.0%)		WATER DEPTH		GEOLOGIST FIELD TEAM			
Classification Of Materials (Description)				Sample #		Remarks			
Depth	Labeling								
1		0.0 to 0.5 Ft: Very Fine Sand - fine silt				S1	0.0 Ft. to 0.5 Ft. Shell: 22.0% Mean Grain Size: 0.130mm		
2		0.5 to 4.1 Ft: Medium Sand with Crushed Shell - medium gray, lot of shell fragments							
3									
4									
5		4.1 to 5.1 Ft: Very Fine Sand - dark gray, silt fine sand shells				S2	4.1 Ft. to 5.1 Ft. Shell: 4.0% Mean Grain Size: 0.130mm		
6		5.1 to 5.2 Ft: Medium Sand - medium gray, good quality							
7		5.2 to 5.3 Ft: Clay lens							
8		5.3 to 5.4 Ft: Clay lens							
9		5.4 to 5.5 Ft: Clay lens				S3			
10		5.5 to 5.6 Ft: Clay lens							

CORE LOG				Coastal Science & Engineering				Sheet # of 1	
PROJECT		2589 - Isle of Palms Mar		COORDINATES		Hole Number		IOP-13	
LOCALITY				Nothing 0.000 Easting 0.000 Grid Datum: NAD 83					
DATE				TOP ELEVATION		DEVICE DESIGNATION		Coastal Science & Engineering	
BORE ANGLE		90.00°		BOTTOM ELEVATION		BARREL SIZE/TYPE		3 in. Aluminum	
BURDEN THICKNESS		15.0 ft.				GEOLOGIST FIELD TEAM			
CORE RECOVERY		15 ft. (100.0%)		WATER DEPTH					
				operational water table					
Classification Of Materials (Description)				Sample #		Remarks			
Depth									
1	0.0 to 1.0 Ft Fine Sand - dark grey			S1		0.0 ft. to 1.0 ft. Shell 11.1% Mean Grain Size: 0.140mm			
2	1.0 to 5.0 Ft (Medium Sand with Crushed Shell) - medium grey, lot of shells					S2 1.0 ft. to 5.0 ft. Shell 12.0% Mean Grain Size: 0.120mm			
3	2.1 Ft Coarse Shell								
4	5.0 to 5.3 Ft Medium Sand								
5	5.3 to 5.4 Ft Medium Sand with Crushed Shell - medium grey								
6	5.4 to 5.4 Ft Medium Sand								
7	5.4 to 5.5 Ft 4.5:1.4 - shell w/ silt			S3		5.4 ft. to 5.5 ft. Shell 12.0% Mean Grain Size: 0.120mm			
8	5.5 to 5.6 Ft Medium Sand								
9	5.6 to 5.7 Ft Medium Sand								
10	5.7 to 5.8 Ft Medium Sand								
11	5.8 to 5.9 Ft Medium Sand								
12	5.9 to 6.0 Ft Medium Sand								
13	6.0 to 6.1 Ft Medium Sand								
14	6.1 to 6.2 Ft Medium Sand								
15	6.2 to 6.3 Ft MUDY mud - dirty clay mud								

CORE LOG				Coastal Science & Engineering				Sheet #1	
PROJECT		258925 - Isle of Palms Feb		COORDINATES		HOLE NUMBER		IOP-20	
LOCALITY				Northing: 2381159, 900 Easting: 24262, 940 Grid Datum: NAD '83					
DATE				TOP ELEVATION		DEVICE DESIGNATION		Coastal Science & Engineering	
BORE ANGLE		90.00°		BOTTOM ELEVATION		BARREL SIZE/TYPE		3 in. Aluminum	
BURDEN THICKNESS		9.6 ft.				GEOLOGIST FIELD TEAM			
CORE RECOVERY		9.3 ft. (96.9%)		WATER DEPTH					
				geophysical data only					
Depth	Interval	Classification Of Materials (Description)			Sample	Remarks			
1		0.0 to 2.1 ft: Fine Sand / Medium Sand mix - w/ minor shell light tan to grey			S1	0.0 ft. to 2.1 ft. Shell 12.0% Mean Grain Size: 0.130mm			
2		2.1 to 3.2 ft: Very Fine Sand - sandy silt with shells			S2	2.1 ft. to 3.2 ft. Shell 12.0% Mean Grain Size: 0.130mm			
3									
4									
5									
6		3.2 to 3.3 ft: Fine Sand with Crushed Shell - minor clay			S3	3.2 ft. to 3.3 ft. Shell 12.0% Mean Grain Size: 0.140mm			
7		- 6.5 Ft Clay lens							
8									
9									
10									
						Alternating clay and sand, very			

CORE LOG		Coastal Science & Engineering				Sheet #1 of 1	
PROJECT		258925 - Isle of Palms Feb		COORDINATES		HOLE NUMBER	
LOCALITY				Nothing 2380558.840 Easting 343330.770 Grid Cont. '83		IOP-25	
DATE							
BORE ANGLE		90.00°		TOP ELEVATION		DEVICE DESIGNATION Coastal Science & Engineering	
BURDEN THICKNESS		9.8 ft.		BOTTOM ELEVATION		BARREL SIZE/TYPE 3 in. Aluminum	
CORE RECOVERY		9.8 ft. (100.0%)		WATER DEPTH		GEOLOGIST FIELD TEAM	
				Geopositioned with GPS			
Depth	Classification Of Materials (Description)			Sample #	Remarks		
1	0.0 to 0.5 ft: Medium Sand with Crushed Shell				S1 0.0 ft. to 0.5 ft. Shell 12.0% Mean Grain Size: 0.08mm		
	0.5 to 1.1 ft: Fine Sand with Crushed Shell - w/ shell and silt			S1	1.1 to 3.4 ft: Fine Sand / Medium Sand mix - clean, light-med grey		
	1.1 to 3.4 ft: Fine Sand / Medium Sand mix - clean, light-med grey				S2 1.1 ft. to 3.4 ft. Shell 12.0% Mean Grain Size: 0.110mm		
3				S2			
5	3.4 to 3.7 ft: Fine Sand / Medium Sand mix - w/ shell compaction, light-med grey			S3	3.4 ft. to 3.8 ft. Shell 12.0% Mean Grain Size: 0.110mm		
7							
8	3.7 to 3.8 ft: Fine Sand / Medium Sand mix - w/ silty, light-med grey			S3			
10							
12	3.8 to 3.9 ft: 4.0 ft. - stiff marine clay, dark grey, do not dig						

Coastal Science & Engineering					Sheet #1	
CORE LOG		PROJECT 258925 - Isle of Palms Feb		COORDINATES		
LOCALITY		DATE		HOLE NUMBER		
BORE ANGLE 90.00°		TOP ELEVATION		DESIGNATION Coastal Science & Engineering		
BUREN THICKNESS 9.6 ft.		BOTTOM ELEVATION		BARREL SIZE/TYPE 3 in. Aluminum		
CORE RECOVERY 9.6 ft. (100.0%)		WATER DEPTH		GEOLOGIST FIELD TEAM		
Depth		Classification Of Materials (Description)		Remarks		
1		0.0 to 4.2 ft: Fine Sand / Medium Sand mix - w/ shells, med grey		S1 0.0 ft. to 4.3 ft. Shell 12.0% Mean Grain Size: 0.130mm		
2				S1		
3						
4		4.2 to 7.3 ft: Fine Sand - w/ silt clay lens		S2 4.2 ft. to 7.3 ft. Shell 19.8% Mean Grain Size: 0.220mm		
5		5.0 ft: Clay lens				
6		6.3 ft: Clay lens		S2		
7		7.0 ft: Clay lens				
8		7.3 to 8.7 ft: Medium Sand - w/ minor shells		S3 7.3 ft. to 8.7 ft. Shell 19.8% Mean Grain Size: 0.160mm		
9		8.7 to 9.4 ft: 4.5:1.4 - silt/clay marine clay				
10						

